

E Blithedale Ave Rehabilitation

May 10, 2021



What is the East Blithedale Avenue Rehabilitation Project?

- Roadway Rehabilitation Project:
 - Repave roadways
 - Repair damaged curb, gutter and sidewalks
 - Replace non-ADA compliant curb ramps
 - Upgrade existing traffic signals to meet current standards
 - Improve ped access and safety where feasible
 - TAM Grant to add Class II bike lanes from Lomita Drive to Tower Drive (City Limits)




emental tion MILL VALLEY

Project Overview


- Project Limits: Sunnyside Ave to Highway 101 Interchange
 - Phase 1 Highway 101 to Camino Alto
 - Phase 2 Camino Alto to Elm Ave
 - Phase 3 Elm Ave to Sunnyside Ave
- Phase 1 Construction: Anticipated in Summer 2021
- Other Planned Corridor Projects:
 - City Sewer Line Rehabilitation 2022
 - MMWD Water Line Replacements Planned for 2022
 - Ashford Avenue: Repaving Lomita to E. Blithedale in Summer 2021



Project Schedule and Outreach Activities



Design Timeline



Construction Outreach:

- Anticipated start of construction is June 2021
- Construction phase community meetings are anticipated in May/June 2021
- Additional outreach for Phases 2 and 3 in Fall 2021




- City Council Approve Phase I Project Design Plans May 17, 2021
- Open Bid May 27, 2021
- The roadway construction is expected to start in mid-June
- Substantially completed by the end of October 2021
- Replacement of the traffic signal poles is expected to be completed by January 2022 due to the long lead time for manufacture and delivery of the poles.



Project Funding

Funding Source	Phase 1 Construction	Future Phases
TAM Measure AA (Rehab)	\$1,210,000	-
TAM Measure AA (Bike Lane Grant)	\$ 400,000	-
Gas Tax	\$100,000	
MST	\$700,000	
Roadway Impact Fee	\$150,000	
City Annual Street Rehab	\$1,500,000-	\$3,250,000
Federal HSIP Grant	-	\$250,000
Total	\$4,060,000	\$3,500,000
Construction Estimate	\$3,700,000	\$5,000,000

Phase 1 Plan - Current Design






Item 6 - Supplemental

Phase 1 Roque Moraes/Lomita Improvements






Phase 1 Plan - Concept Widening for Class IV Cycle Track






Item 6 - Supplemental

Phase 1 Ashford Ave Improvements





Bike Lane Types








CLASS II BIKEWAY


CLASS IV CYCLE TRACK

Item 6 - Supplemental tio


Phase 1 Bicycle Facility Improvements



Class II Bike Lane



7' Class IV Cycle Track-Current Project



10' Class IV Cycle Track

Phase 1 Construction Logistics

- 1. Pavement rehabilitation activities for the project to be performed during the hours between 8 PM and 6 AM Sunday through Thursday.
- 2. Traffic lanes closure in the commute direction during the day will be limited to 9 AM to 3 PM.
- 3. Nighttime construction equipment will be restricted to low noise equipment.
- 4. Changeable Message Board signs will be posted two weeks prior

to the start of construction at both ends of the project site and along other locations alerting motorists in advance and urging folks to seek alternate travel times and routes.










THIRD STREET REHABILITATION TAM EXECUTIVE COMMITTEE MEETING

May 10, 2021

Project Limits

3rd Street from Just east of Union St to 2nd St 2nd Street from West St to Shaver St





HSIP: "Highway Safety Improvement Program"




Project Outreach

- 1. Technical Working Group Meeting July 2017
- 2. Community Working Group Meeting October 2017
- 3. Community Meeting #1 November 2017
- 4. Working Group Meeting February 2018
- 5. Community Meeting #2 March 2018
- 6. City Council Approves Master Plan Update July 2018
- 7. Feasibility Report Presentation to City Council June 2019
- 8. Bicycle and Pedestrian Committee August 5, 2020
- 9. Community Meeting #3 September 23, 2020
- 10. Presentation to City Council November 3, 2020
- 11. BPAC- December 2, 2020 & February 3, 2021
- 12. Community Meeting #4 March 24, 2021
 - 13. City Council Approves Project May 3, 2021



Additional Information

April Miller, P.E. Senior Civil Engineer April.Miller@cityofsanrafael.org 415-485-3409



www.cityofsanrafael.org/third-st-rehab/

Frequently asked questions



More information

Draft Intersection Layout (April 2021)



Project Goals

- 1. Improve **safety** for all bicyclists and pedestrians
- 2. Repair **pavement** and **drainage**
- 3. Improve **pedestrian crossings** and repair sidewalks
- 4. Upgrade traffic signals and provide safety lighting
- Improve traffic flow for cars, transit, and emergency service
- Add street trees
- 7. Enhance access for designated **Safe Routes to Schools**
- 8. Develop an **economically viable** project
 - 9. Infrastructure replacement by MMWD & SRSD.




Intersection Enhancemental Information



Bulb-out



Detectable Warning Surface



Curb Ramp



High Visibility Crosswalk hird 6troft 20 habilitation May 10, 2021

Traffic Signals



YELLOW BAND NIGHTIME VISIBILITY



COUNTDOWN SIGNALS

New Traffic Signals: Brooks Street East Street








SAFETY LIGHTING

Downtown Intersections



Raised Intersections



A Street

B Street

C Street

D Street




Second Street Bicycle Facility




East Street

Third to the table table to the table to the table to the table to the table to tab

Second Street Bicycle Facility





CLASS I BIKE LANE

SCALE: 1" = 5"



Class IV Bikeway Barriers









Asphalt Berm

Vertical barrier separates vehicles and bicyclists.

Low cost.

Base Bid

Bollard and Marker

Visual separation between vehicles and bicyclist.

Least cost.


Deductive Alternative Bid

Concrete Curb

Vertical barrier separates vehicles and bicyclists.
Resilient
Higher cost.



Second Street Bicycle Facility





2nd & East St Bicycle Facility





2nd & G Street Bicycle Facility



May 10, 2021

Third Street Trees





Project Budget & Funding

Previously Allocated				
Feasibility Study	\$	300,000		
PE/ Design	\$	1,000,000		
)da.a	4		
Construction Budget				
Measure A/AA	\$	11,654,106		
SB1 RMRA	\$	1,000,000		
Gas Tax City Fund	\$	650,000		
Traffic Mitigation Fund	\$	200,000		
Total Funding Available	\$	13,504,106		
Construction Management services	\$	600,000		
Construction Estimate		12,900,000		
Estimated Total		13,500,000		



Project Next Steps

Feasibility Study April 2017 to June 2019 Concept
Design
January to
August
2020

Council Review 11.02.20 CEQA
Review
and Final
Design
Winter/
Spring
2020

Council Approval of Project 05.03.21 Secure TAM funding 05.10.21 & 05.27.21 Contract with CM Firm June 2022

Plans out to Bid July/Aug 2022

Construct Sept/Oct 2021 to Fall 2022



Construction Process

1. About 1 year of construction

2. General sequence of work

- Utilities MMWD, sewer district, and PG&E
- Sidewalk and curb ramps
- Traffic signals
- Paving and striping
- Street trees

3. Lane closures during off peak periods

- East bound (Second Street): 9 am to 6 pm
- West bound : 6 am to 3 pm
- 4. Night work for paving and specific operations
- 5. Driveways will be closed for periods of up to 4 hours



Both the City and contractor will outreach to residents and businesses during construction to provide advance notice of construction activities.



Thank you Questions & Comments

